

Rc
OVERSIZE
371.0097
R6762r

ROCHESTER
PUBLIC
LIBRARY

—
THE GIFT OF
ROCHESTER CITY
SCHOOL DISTRICT



1

Rr
*
321.0097
R67625

Rochester Public Library
Reference Book
Not For circulation

Rochester Public Library
115 South Avenue
Rochester, NY 14604-1896

1-1

ROCHESTER
PUBLIC
LIBRARY

—
THE GIFT OF
ROCHESTER CITY
SCHOOL DISTRICT

MARTIN B. ANDERSON SCHOOL NO. 1

Winton Road near East Avenue

The original and present building was erected in 1884 at a cost of \$6,000.00. This school was formerly known as District No. 2 of the Town of Brighton, and until the annexation of part of said town to the City of Rochester, April 5, 1905, at which time the school came under the supervision of the Board of Education and became the property of the city.


The building is a two story brick structure with slate roof, heated by hot air furnaces.



SCHOOL NO. 1 (OLD) - LOOKING NORTHWEST FROM
REAR - South East. 7/22/21


R. S. & E. R. R.

29




EAST AV.


Area of building	2430 s.f.
• • schoolground	<u>29841</u> •
• • lot	32271 •



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL


Scale - 1" = 32'-0"

NO. 1


Exit = ◇



SCHOOL NO 1 (NEW) - LOOKING NORTH SHOWING
STEAM SHOVEL EXCAVATING 7/22/21



Area of building	33438	s.f.
" " schoolground	400764	"
" " lot	434202	"



FIRST FLOOR PLAN.

SCALE 1" = 32'

MARTIN B. ANDERSON SCHOOL #1.



School No. 2 Looking N.W. July 1-1921



School No. 2 Looking South-West. July 1-1921

MADISON PARK VOCATIONAL SCHOOL NO. 2

King Street near Main Street West

The original building was erected in 1843. A new building was erected in 1857 and remodeled in 1868.

The present building was erected in 1873 and 1874 at a cost of \$6,080.00. In 1901 the Beekman Water Closet System was installed in the basement at a cost of \$933.23.


The building was altered to suit the requirements of a vocational school in 1910 by E. E. Robinson at a cost of \$2,388.00, and further alterations were made in 1911 by John B. Pike at a cost of \$2,794.00. Electricity was installed by Wheeler-Green Electric Co. in 1914 at a cost of \$431.60. In 1916 contract for installing fire escapes was awarded to George B. Garrison for \$699.00.

The present building is a two story brick structure with slate and tin roof, heated by hot air furnaces.





MADISON ST.


KING ST.



Area of building	4577 s.f.
" " schoolground	3820 "
" " lot	8397 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN

PUBLIC SCHOOL N^o 2
Scale - 1" = 32'-0"

Exit = ◇

1



SCHOOL NO 3 LOOKING SOUTHWEST 7/26/21

2



SCHOOL NO 3 - LOOKING NORTHWEST 7/26/21

3



SCHOOL NO 3 - LOOKING NORTHEAST. 7/26/21

4



SCHOOL NO 3 LOOKING SOUTHWEST 7/26/21

NATHANIEL ROCHESTER SCHOOL NO. 3
Tremont Street near Plymouth Avenue

Original building was erected prior to 1842 at a cost of \$3,000.00. Four rooms were added in 1877, costing \$5,500.00. In 1882 the building was remodeled at a cost of \$4,328.00.

The building was entirely rebuilt in 1893, contracts being awarded as follows:

Mason Work	Bruff, Horn & Co.	\$8,801.60
Carpenter Work	Thos. Salter	10,400.00
Cut Stone	Brayer & Fuhrman	2,431.00
Painting	J. C. Simmons	765.00
Plumbing	T. W. Ford	831.00
Heating and Ventilating	Barr & Creelman	2,459.00
		<u>\$25,687.60.</u>

This building, which was a two story brick, with slate roof containing 20 rooms, heated by direct and indirect steam, and equipped with flush water closet system, was destroyed by fire February 15, 1912. The Gorsline & Swan Construction Co. cleared away stones, brick and other rubbish at a cost of \$3,315.00.

Contracts for the present building were awarded September 9, 1912, as follows:

Mason Work	Dunning & Glasser	\$68,600.00
Carpenter Work	H. P. Sickles Co.	23,999.00
Plumbing, Heat- ing, Ventilating and Electrical Work	Frank H. Falls	33,048.00
		<u>\$125,647.00</u>

NATHANIEL ROCHESTER SCHOOL NO. 3


(Continued)

This building is a three story brick fireproof structure with slag roof; heated and ventilated by the fan system and direct radiation in rooms, under automatic temperature control.


①




(2)



THIRD FLOOR PLAN



SECOND FLOOR PLAN



FIRST FLOOR PLANS

PUBLIC SCHOOL

No 3

EXIT



SCHOOL NO 4 FRONT LOOKING
NORTHWEST 7/27/21



SCHOOL NO 4 FRONT - LOOKING
SOUTHWEST 7/27/21



SCHOOL NO 4 LOOKING SOUTHWEST SHOWING
PORTABLE IN REAR 7/27/21

GENESEE SCHOOL NO. 4

Jefferson Avenue near Bronson Avenue


The original building was erected in 1842 at a cost of \$2,300.00/. A new two story brick building which was commenced in 1857 and finished in 1860, was destroyed by fire in 1873.

This school was rebuilt the following year at a cost of \$22,500.00. Since 1877 about \$13,109.00 has been expended on additions to the building, and for the installation of a steam heating and ventilating system in 1883.

The R. T. Ford Co. was awarded contract for the installation of two new boilers on August 22, 1907 for \$1,407.00; and on October 13, 1909 the contract for electric wiring was awarded to Wheeler-Green Electric Co. for \$1,473.00.

The present building is a one and three story brick structure with slate and gravel roof; heated by direct and indirect steam.


PENN ST.




JEFFERSON AVE.

BRONSON AVE.


Area of building	11 429 s.f.
" " schoolground	19 351 "
" " lot	30 780 "




THIRD FLOOR PLAN



SECOND FLOOR PLAN



FIRST FLOOR PLAN



PUBLIC SCHOOL
Scale - 1" = 48'-0"

Nº 4

Exit = ◇



SCHOOL NO 5 LOOKING NORTH

7/14/21



SCHOOL NO 5 LOOKING WEST

7/14/21

CENTRAL SCHOOL NO. 5

Jones Street corner Dean Street

The original building was a stone structure located in Brown's Square, erected in 1842 at a cost of \$5,400.00. This was improved in 1365.


In 1875 a new building was erected in its present location at a cost of \$18,000.00. Contract for electric wiring was awarded to Wheeler-Green Electric Co. for \$1,067.00 on October 13, 1909.

On March 17, 1913 contracts for a four room addition were awarded as follows:


Mason Work	Curran & Swartout	\$4,550.00
Carpenter Work	Fred Gleason	4,805.00
Plumbing	Barr & Creelman	546.00
Heating	William Devendorf	420.00
Electrical Work	Wheeler-Green Electric Co.	237.90
		<u>\$10,558.90</u>

Contract for installing fire escapes was awarded to Geo. B. Garrison for \$1,219.00 on August 22, 1916.


The present building is a one and three story brick structure with slate, tin and rubberoid roof; heated by hot air furnaces.




SCHOOL No. 5-Area of buildings	9 943 s. f.
" " schoolground	6 629 "
" " lot	16 572 "
SCHOOL No. 5A:-Area of building	2 047 "
" " schoolground	1 282 "
" " lot	3 329 "




THIRD FLOOR PLAN




SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN



PUBLIC SCHOOL
SCALE 1" = 48'-0"

Nº 5

Exit: ◇

5-B



SCHOOL NO 5-B LOOKING WEST 7/14/21



SCHOOL NO 5-B LOOKING NORTH 7/14/21



SCHOOL NO 5-B LOOKING SOUTH SHOWING HOUSES RECENTLY BOUGHT FOR NEW NO 5 SITE 7/14/21



SCHOOL NO 5-B LOOKING WEST-SHOWING CRIPPLED CLASS AND TENT IN YARD 7/14/21

JONES ST.

FRANK ST.

JAY ST.

No. 5 B.

200.96

Area of buildings
" " schoolground
" " lot

S. f.

$$1'' = 100'$$



SCHOOL NO. 6 LOOKING NORTH

7/14/21



SCHOOL NO. 6 LOOKING WEST

7/14/21



SCHOOL NO. 6 LOOKING SOUTH

7/14/21

FRANKLIN SCHOOL NO. 6

Montrose Street near Frank Street

The present building was erected in 1901, contracts being awarded on March 26, 1901 for a seventeen room school with assembly hall as follows:


Mason Work	Frederick P. Stallman	\$22,962.00
Carpenter Work	F. H. Rapp	19,900.00
Steel Work	American Bridge Co.	1,322.00
Painting	Monroe Painting Co.	1,106.00
Plumbing	R. T. Ford Co.	2,159.17
Heating and Ventilating	R. T. Ford Co.	8,030.71
		<u>\$55,479.88</u>

On November 18, 1908 contract for finishing three rooms was awarded to A. C. Stitt for \$1,870.00. Contract for electric wiring in Assembly Hall was awarded on October 15, 1909 to Rochester Electric Contracting Co. for \$86.00, and on December 31, 1914 contract for electric wiring in remainder of building was awarded to E. C. Sykes Co. for \$1,825.00.

Contract for fire alarm system was awarded February 1, 1915 to the American Telephone Fire Alarm Co. for \$701.50. On June 2, 1919 contract was awarded to John Rankin for fireproof room for storage of waste paper and oils for \$565.00.


The building is a two story brick structure with slate and tin roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.

COSTAR ST.




MONTROSE ST.


Area of building	18 195 s.f.
" " schoolground	28 355 "
" " lot	46 550 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

No 6

Scale 1" = 48'-0"

Exit = ◇



SCHOOL NO 7 LOOKING NORTHWEST

6/30/21



SCHOOL NO. 7 LOOKING NORTHEAST

6/30/21

LAKE VIEW SCHOOL NO. 7

Pierpont Street cor. Kislingbury Street

Original building was erected in 1859 and was located on Lake Avenue. An addition was made in February of 1895, contracts being awarded as follows:

Mason Work	Anthony Link	\$175.00
Carpenter Work	Anthony Link	292.00
Cut Stone Work	P. G. Hauch	39.50
Painting	C. W. Hare, Jr.	89.00
Plumbing	Maher & Glasgow	404.00
Heating and Ventilating	Shaughnessy & Connolly	75.00
		<u>\$1,074.50</u>

On June 17, 1895, contracts for a four room addition were awarded as follows:

Mason Work	P. G. Hauck	\$2,930.00
Carpenter Work	Keene & Son	3,051.00
Cut Stone Work	Brayer & Fuhrman	685.00
Painting	J. C. Simmons	397.00
Plumbing	Mahar & Glasgow	109.00
Heating and Ventilating	R. T. Ford	410.00
		<u>\$7,582.00</u>

Contracts for the erection in its present location of a new 17 room building with assembly hall were awarded March 21, 1902, as follows:

Mason Work	Geo. B. Garrison	\$22,946.00
Carpenter Work	F. H. Rapp	20,059.00
Steel Work	Kellogg Iron Works	1,848.00
Painting	Monroe Painting Co.	984.00
Plumbing	Wm. G. Reid & Son	2,419.00
Heating and Ventilating	Barr & Creelman	7,692.00
		<u>\$55,948.00</u>


LAKE VIEW SCHOOL NO. 7

(Continued)


On October 15, 1909, contract for electric wiring in assembly hall was awarded to Rochester Electric Contracting Co. for \$84.00. Contract for a two room addition was awarded to Frank J. Sauer for \$5,752.87 on December 12, 1910. Wheeler-Green Electric Co. was awarded contract for electric wiring in remainder of building for \$1,667.00 on December 27, 1915.

Contract for fireproof room for storage of waste paper and oils was awarded to Dunning & Scott for \$409.00 on June 19, 1919.



The building is a two story brick structure with slate and tin roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.




Area of building	17 291 s.f.
" " schoolground	47 829 "
" " playground	53 658 "
" " lot	118 778 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL N^o 7

Scale 1" = 48'-0"

$$E_{\lambda} T = \diamond$$



SCHOOL NO. 8 LOOKING SOUTHEAST

7/7/21



SCHOOL NO 8 LOOKING SOUTHWEST

7/7/21

CARTHAGE SCHOOL NO. 8

Conkey Avenue cor. Avenue B

The original school was held in a frame building erected about 1835 at a cost of \$3,000.00. A new building was erected in St. Paul Street in 1855, to which an addition was made in 1884, contract being awarded to Joseph May for \$995.00.

The present building was erected in 1894, contracts being awarded as follows:

Mason Work	J. Karweick	\$6,100.00
Carpenter Work	Anthony Link	5,643.00
Cut Stone Work	N. L. Brayer	342.25
Painting	Stephen Strebb	350.00
Plumbing	W. T. Fox & Col	485.00
Heating and Ventilating	R. T. Ford	<u>1,475.00</u>
		\$14,395.25

On April 3, 1900, contracts for an addition were awarded as follows:

Mason Work	Geo. B. Garrison	\$7,275.00
Carpenter Work	Wm. F. Maas	8,767.00
Steel Work	Rochester Bridge & Iron Works	866.00
Painting	Monroe House Painting Co.	400.00
Plumbing	R. T. Ford	1,541.18
Heating and Ventilating	R. T. Ford	<u>5,828.00</u>
		\$24,677.18

The contract for erection of an assembly hall was awarded to Anthony Link for \$6,905.00 on December 12, 1910.

CARTHAGE SCHOOL NO. 8

(Continued)

On May 26, 1919 contract for electric wiring was awarded to O'Connell Electric Co. for \$3,550.00. Contract for fireproof room for storage of waste paper and oils was awarded to John Rankin for \$405.00 on June 20, 1919.

The building is a two story brick structure with tin and slate roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.


AVENUE B




CONKEY AV

AVENUE A


Area of present building	14 024 s. f.
" " new additions	9 325 "
" " frame dwelling	1 080 "
" " schoolground	16 232 "
" " lot	40 661 "




ATTIC FLOOR PLAN




SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN



PUBLIC SCHOOL
Scale 1" = 64'-0"

Nº 8

Exit = ◇



SCHOOL NO. 9

6/8/21.

ANDREWS SCHOOL NO. 9

Joseph Avenue cor. Baden Street

Original building was erected in 1842 at a cost of \$1,500.00. A new building was commenced in 1860, during which year \$13,670.00 was spent on the earliest constructed part of the building. An addition was made in 1881 at a cost of \$12,000.00. Another addition was made in 1894, contracts for which were awarded as follows:

Mason Work and	J. C. Geminder	\$586.00
Cut Stone Work		
Carpenter Work and	Herman Tosch	462.00
Tin Work	A. Marselji & Son	62.00
Painting	Shaughnessy & Connolly	420.00
Plumbing		<u>\$1,530.00</u>

On August 3, 1896 contracts for an addition were awarded as follows:

Mason Work	Beale & Beisheim	\$7,782.00
Carpenter Work	F. J. Sauer	7,741.50
Cut Stone	Brayer & Fuhrman	614.00
Painting	Stephen Strieb	430.00
Plumbing	W. T. Fox & Co.	1,400.00
Heating & Ventilating	R. T. Ford	2,720.00
		<u>\$20,687.50</u>

Contract for addition of four rooms was awarded to Frank J. Sauer for \$11,994.85 on July 18, 1906. An addition of 19 rooms with assembly hall was made in 1907, contract for which was awarded to F. H. Rapp & Co. for \$95,589.00 on March 22nd. The old part was torn down and this addition made to the part left standing. Contract for a four room addition was awarded to A. W. Hopeman & Son for \$10,896.00 on March 8, 1909.


ANDREWS SCHOOL NO. 9

(Continued)


On October 13, 1909 contract for electric wiring was awarded to Rudolph Schmidt & Co. for \$2,645.00. Contract for elevator, and fireproof room for storage of waste paper and oils was awarded to W. F. Maas for \$1,020.00 on July 31, 1914.

On February 1, 1915 contract for fire alarm system was awarded to American Telephone Fire Alarm Co. for \$854.00.


The building is a two story brick structure with tin and slate roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.




Area of present building	30 843 s.f.
" " new addition	16 654 "
" " schoolground	11 113 "
" " playground buildings	3 759 "
" " playground	54 339 "
" " Baden St. house	1 079 "
" " " " lot (outside of ho.)	2 967 "
" " lot (inc. all buildings)	120 754 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

Scale 1" = 64'-0"

No 9

Exit = ◇




SCHOOL NO 10 LOOKING NORTHWEST

8/8/21



SCHOOL NO 10 LOOKING SOUTHWEST

8/15/21



SCHOOL NO 10-LOOKING WEST

8/15/21

EUGENE FIELD SCHOOL NO. 10

Chatham Street near Central Avenue

The original school building existed prior to 1841 when the first Board of Education of this city was organized. It was located on Andrews Street just east of North Clinton Street, and was either re-built or remodeled in 1842 into a two story stone structure valued at \$2,000.00.

In 1852 this building and site were exchanged for a site on Clinton Street, costing the city in the exchange about \$700.00. In 1853 a new building costing about \$7,000.00 was built on the Clinton Street site. In 1864 the interior of this building was remodeled and in 1870 a third story was added. Further enlargements were made in 1878.

The original building of the present school on Chatham Street was erected in 1891, and cost approximately \$67,000.00. Four additional rooms were finished in 1893 at a cost of \$1,626.00.

In 1913 the contracts for a seven room addition and assembly hall were awarded as follows:

Mason Work and	R. T. Ford Co.	\$40,800.00
Carpenter Work	Barr & Creelman	1,930.00
Plumbing		
Heating and	Barr & Creelman	26,800.00
Ventilating	Roch. Electric Motor Co.	2,400.00
Electrical Work		<u>\$71,930.00</u>

EUGENE FIELD SCHOOL NO. 10
(Continued)


Contract for sprinkler system was awarded to General Fire Extinguisher Co. for \$4,622.00 on November 3, 1913. Fireproof room for the storage of waste paper and oils was added in 1919 at a cost of \$831.50, which work was done by James Meaney.

The building is a one and two story brick structure with slag, tin and slate roof; heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.

CENTRAL AV.


60'

66'




CHATHAM ST.



Area of building	24 354 s.f.
" " schoolground	9 366 "
" " lot	33 720 "



SECOND FLOOR PLAN



THIRD FLOOR PLAN



FIRST FLOOR PLAN



GROUND FLOOR PLAN

PUBLIC SCHOOL

N^o 10

Scale 1" = 64'-0"

Exit = 9

SAMUEL A. LATTIMORE SCHOOL NO. 11

Webster Avenue

The site for this school was purchased March 29, 1907. Contracts for a new 8 room school building were awarded June 14, 1907, as follows:

Mason Work	E. Strauchen	\$13,627.00
Carpenter Work and Painting	A. Hopeman	10,648.00
Plumbing, Heating and Ventilating	Barr & Creelman	6,375.00
		<u>\$30,650.00</u>

On July 24, 1911, contracts for an addition were awarded as follows:


Mason Work	H. Stallman Sons	\$7,951.00
Carpenter Work	John B. Pike	7,694.00
Plumbing, Heating and Ventilating	Towe, Devendorf & Boruff	6,668.48
		<u>\$22,313.48</u>

Contracts for a 7 room addition were awarded April 28, 1913, as follows:


Mason and Carpenter Work	P. G. Hauck	\$33,839.00
Plumbing	R. T. Ford & Co.	696.00
Heating and Ventilating	Edward Towe	3,750.00
Electrical Work	Wheeler-Green Electric Co.	1,157.00
		<u>\$39,442.00</u>

E. C. Sykes & Co. were awarded contract for additional electric wiring for \$788.00 on December 27, 1915.

The building is a one and two story brick structure with slag and slate roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.



Area present building	20 579	s.f.
• new additions	6 714	•
• future	2 403	•
• schoolground	70 502	•
• playground	106 519	•
• lot	206 717	•



PUBLIC SCHOOL

Scale 1" = 48'-0"

Nº 11



SCHOOL NO 12 LOOKING NORTHEAST
CORNER CLINTON AND MARSHALL

8/4/21



SCHOOL NO 12 LOOKING NORTHWEST

8/4/21



SCHOOL NO 12 LOOKING EAST
SHOWING CLINTON AVENUE SIDE

8/4/21

WADSWORTH SCHOOL NO. 12

Howell Street cor. Clinton Avenue South

The original school was erected in 1842 on a part of the present site, at a cost of \$3,000.00. A new building was erected in 1857. Prior to 1885 about \$15,000.00 was spent for additions to and for remodeling this building.

In 1899 a new building was erected, costing approximately \$40,000.00. In 1900 a new automatic temperature control was installed at a cost of \$1,057.00, and on October 27, 1905 the contract for finishing the attic was awarded to E. E. Robinson for \$1,027.00.


Contract for heating and ventilating was awarded to Towe & Devendorf for \$5,873.00 on June 10, 1912. On February 19, 1915 contract for electric wiring was awarded to Rochester Motors Co. for \$1,550.00

Contract for fireproof room for storage of waste paper and oils was awarded to John Rankin for \$595.00 on July 11, 1919.

The building is a two story brick structure with tin and slate roof heated and ventilated by fan system under automatic temperature control from each room and direct radiation in rooms, under hand control.

CLINTON AV.

HOWELL ST.




WADSWORTH PARK



BROADWAY

MARSHALL ST.


Area of building	12 998 s.f.
• • schoolground	<u>18 322</u> "
• • lot	31 320 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL
Scale 1" = 48'-0"

Nº 12



SCHOOL NO. 13
LOOKING NORTHWEST

6/10/21



SCHOOL NO. 13
LOOKING NORTHWEST

6/10/21

HORACE MANN SCHOOL NO. 13

Hickory Street near South Avenue

The original building was erected in 1845; a front was added to this building in 1852; a south end in 1867; entirely remodeled in 1871-2 and in 1889 a four room addition was made costing approximately \$16,500.00 for the original building, additions, etc.

In 1903, a new building was erected, the original school lot having been enlarged by the purchase of two lots west of the land upon which the old building stood. Contracts were awarded on March 27, 1903 as follows:


Mason Work	Aug. Pappart & Sons	\$27,400.00
Carpenter Work		
Painting & Tinting	Thos. W. Finucane Co.	22,390.00
Plumbing, Gas Heating & Ventilating	R. T. Ford	13,590.00
		<u>\$63,380.00</u>

Contract for electric wiring was awarded to Wheeler-Green Electric Co. for \$1,787.00 on October 13, 1909.

This building is a two story brick structure with slate roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.

14


HICKORY ST.




GREGORY ST.

Area of building	16 591 s.f.
" " schoolground	42 917 "
" " lot	59 508 "


1" = 50'



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

N^o 13

Scale 1" = 48'-0"



SCHOOL NO 14 LOOKING ~~WEST~~ EAST
FRONT ELEVATION 8/1/21



SCHOOL NO 14 LOOKING EAST 8/1/21



SCHOOL NO 14 LOOKING NORTH SHOWING MAIN
ENTRANCE 8/1/21



SCHOOL NO 14 LOOKING NORTH SHOWING
KINDERGARTEN BAY 8/1/21

CITY NORMAL SCHOOL NO. 14

Scio Street cor. University Avenue

The original building was erected in 1842 not far from the present location on Scio Street and cost \$1,500.00. This was rebuilt in 1851 at a cost of \$5,280.00. In 1863 this building was enlarged at a cost of \$3,747.00 and again in 1878 at a cost of \$5,874.00.

A new building was erected in 1887-8 at a cost of \$31,000.00. An addition was made in 1895, contracts being awarded as follows:

Mason Work	Pr G. Hauck	\$5,601.75
Carpenter Work	Anthony Link	7,947.00
Steam Heating	R. T. Ford	2,750.00
Plumbing	R. T. Ford	640.00
Painting	G. W. Hare, Jr.	296.00
Cut Stone	Gilbert Brady	" 615.00
		<u>\$17,849.00</u>

In 1910 the contract for installing telephones was awarded to Rudolph Schmidt & Co. for \$330.00.

This building was a three story brick structure with slate roof, had 26 rooms including an assembly hall, was equipped with the Smart & Ruttan heating system and Smead dry closet system. On the night of January 4, 1915 this school was destroyed by fire.

On June 14, 1915 contracts for the present school were awarded as follows:


Mason Work and		
Carpenter Work	R. T. Ford	\$168,500.00
Plumbing	Howe & Bassett	7,786.00
Electrical Work	O'Connell Electric Co.	5,500.00
Heating and		
Ventilating	Edward Towe	32,400.00
		<u>\$214,186.00</u>


CITY NOERMAI SCHOOL NO. 14

(Continued)

Contract for vacuum cleaner was awarded to Edward Towe for \$1,300.00 on August 30, 1915, and on November 15, 1915 Wright & Alexander Co. were awarded contract for Sprinkler System for \$3,061.00.

This building is a one and two story and basement brick and stone structure with slag roof; heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.


 $1^{\circ} = 100'$




PUBLIC SCHOOL

Scale 1" = 64'-0"

Nº 14



SECOND FLOOR PLAN



FIRST FLOOR PLAN

PUBLIC SCHOOL

Scale 1" = 64'-0"

No 14



SCHOOL NO 15 — LOOKING SOUTH

8/4/21

MONROE SCHOOL NO. 15

Monroe Avenue near Alexander Street


The original building was erected in 1842 at a cost of \$2,000.00 on Alexander Street.

In 1874 a new building was erected on the present location costing \$15,000.00. This building was destroyed by fire in 1881 and rebuilt the same year at a cost of \$17,500.00. A four room addition was made in 1886-7 at a cost of \$14,680.00, and in 1891 another addition of eight rooms was made, costing \$17,384.00.


New closets were installed in 1906, contract being awarded to Caldwell Bros. for \$4,725.00.

The building is a three story brick structure with direct and indirect slate roof, and is equipped with steam heating system.


 $1^{\circ} = 100$




THIRD FLOOR PLAN



SECOND FLOOR PLAN



FIRST FLOOR PLAN



N^o 15

PUBLIC SCHOOL
Scale 1" = 48'-0"

N^o 1



SCHOOL NO 16 FRONT LOOKING WEST

7/27/21




SCHOOL NO 16 LOOKING WESTERLY

7/27/21



SCHOOL NO 16 SHOWING SEVEN SISTERS TREE
IN FOREGROUND

7/27/21



SCHOOL NO 16 LOOKING EAST

7/27/21

JOHN WALTON SPENCER SCHOOL NO. 16

Post Avenue

Contracts for the present school building were awarded in August, 1910 as follows:

Mason Work	A. W. Hopeman & Sons	\$22,868.00
Carpenter Work	Anthony Link	10,150.00
Plumbing, Heating and Ventilating	R. T. Ford Co.	6,582.00
		<u>\$39,600.00</u>

On February 17, 1913 contracts for a three room addition were awarded as follows:

Mason Work	P. G. Hauck	\$7,215.00
Carpenter Work	H. G. Hammon & Son	1,987.00
Heating	R. T. Ford Co.	1,227.00
Electrical Work	Wheeler-Green Electric Co.	283.70
		<u>\$10,712.70</u>

Contracts for a second addition were awarded on June 25, 1915 as follows:

Mason Work and Carpenter Work	Wm. F. Martens & Co.	\$18,235.18
Plumbing	R. T. Ford Co.	997.00
Heating and Ventilating	Arensmeyer, Warnock & Zahrdt	1,696.00
Electrical Work	Wheeler-Green Electric Co.	747.00
		<u>m \$21,675.18</u>

During 1917 contracts for a third addition were awarded as follows:


Mason Work	Gorsline & Swan Constr. Co.	\$42,398.00
Carpenter Work	Fred Gleason	17,996.00
Plumbing	R. T. Ford Co.	3,410.00
Heating and Ventilating	Edward Towe	30,300.00
Painting	Smith & Bartl	700.00
Vacuum Cleaner	Wheeler-Green Electric Co.	1,393.00
Electrical Work	O'Connell Electric Co.	2,811.00
Roofing	Flesch & Schmitt	4,554.00
		<u>\$103,562.00</u>

JOHN WALTON SPENCER SCHOOL NO. 16

(Continued)


On June 3, 1918 contract for completing plumbing on addition was awarded to Murtaugh & Reddington for \$3,500.00.

This building is a one, two and three story brick structure, with slag and built-up asbestos roof heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.




Area of new addition	7 094	s. f.
Area of present building	26 709	s. f.
" " schoolground	69 302	"
" " playground	63 914	"
" " lot	167 019	"


$$1'' = 100'$$




ATTIC FLOOR PLAN



THIRD FLOOR PLAN



SECOND FLOOR PLAN



FIRST FLOOR PLAN



PUBLIC SCHOOL
Scale 1" = 64'-0"

Nº 16

Exit=0



School No. 17 Looking S.W. July 1-1921



School No. 17 Looking S.E.
Orange St. Side Showing Two houses recently purchased July 1-1921



School No. 17 } houses are to be removed to
Campbell St. Side } make room for New Addition } July 1
1921

WHITNEY SCHOOL NO. 17

Orange Street cor. Saxton Street

The original building was erected in 1856 at a cost of \$3,875.00. This building was destroyed by fire in February, 1858, and replaced the same year by a two story brick structure, which was remodeled in 1871, enlarged in 1878 and again remodeled in 1886 at a cost of \$4,000.00.

The present building was erected in 1894 when contracts were awarded as follows:

Mason Work	Bruff, Horn & Co.	\$13,000.00
Carpenter Work	Bruff, Horn & Co.	10,559.50
Cut Stone	N. L. Brayer	1,830.88
Heating	Hayes & Falls	1,300.00
Plumbing	R. T. Ford	1,004.68
Painting	L. J. Kraemer	599.26
		<u>\$28,294.32</u>

Contract for electric wiring was awarded to Wheeler-Green Electric Co. for \$1,393.00 on October 13, 1909. On May 15, 1914 contract for installing a telephone system was awarded to Rudolph Schmidt & Co. for \$270.00.


On March 29, 1915 contracts for an addition were awarded as follows:

Mason Work and Carpenter Work	W.F. Martens & Co.	\$53,877.00
Heating and Ventilating	Wm. F. Devendorf	18,498.00
Plumbing	Wright & Alexander Co.	1,978.00
Electrical Work	Fish & Horton Co.	2,337.00
Sprinkler System	Wright & Alexander Co.	3,489.00
Vacuum Cleaner	Wheeler-Green Electric Co.	1,243.62
		<u>\$81,422.62</u>


WHITNEY SCHOOL NO. 17

(Continued)


This building is a two story brick structure with
and tin
slate built-up asbestos/roof; heated and ventilated by fan
system and direct radiation in rooms, under automatic
temperature control.




Area of dwelling	717 s.f.
Area of present building	26 888 s.f.
" " new addition	28 224 "
" " schoolground	32 003 "
" " lot	87 832 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN




BASEMENT FLOOR PLAN

PUBLIC SCHOOL

N^o 17

Scale 1" = 48'-0"

Exit = 0



THIRD FLOOR PLAN

PUBLIC SCHOOL

Scale 1" = 48'-0"

Nº 17



SCHOOL NO. 18

6/8/21



SCHOOL NO. 18

6/8/21

CONCORD SCHOOL NO. 18

North Street cor. Draper Street

The original building was erected in 1867 at a cost of \$8,034.00. In 1873 an addition of 6 rooms was made, costing \$10,967.00, and in 1884, \$4,000.00 was expended in additions. IN 1888, 8 rooms were added at a cost of \$8,335.00.

In 1909 two rooms of the old building were torn down and an addition of six rooms was built, contracts being awarded June 14, 1909 as follows:

Mason Work	Edward Strauchen	\$16,482.00
Carpenter Work	Homer Knapp	14,046.00
Plumbing, Heating and Ventilating	R. T. Ford	<u>5,891.00</u>
		\$36,419.00

In 1910 contract for installing a telephone system was awarded to Rudolph Schmidt & Co. for \$320.00.

Contracts for the completion of the school were awarded on September 22, 1913 as follows:

Mason Work and Carpenter Work	R. T. Ford	\$108,264.00
Plumbing	R. T. Ford	11,920.00
Heating and Ventilating	R. T. Ford	47,337.00
Electrical Work	R. T. Ford	<u>3,500.00</u>
		\$171,021.00

On February 6, 1914 contract for installation of sprinkler system was awarded to General Fire Extinguisher Co. for \$8,778.00.


CONCORD SCHOOL NO. 18

(Continued)


This building is a two story and basement brick structure, with slag roof, heated and ventilated by fan system and direct radiation in the rooms under automatic temperature control.




Area of buildings	43 696	s.f.
" " schoolground	44 801	"
" " lot	88 497	"



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL
Scale - 1" = 64'-0"

N^o 18



SCHOOL NO 19 FRONT LOOKING NORTHWEST
7/26/21



SCHOOL NO 19 FRONT LOOKING NORTH 7/26/21



SCHOOL NO 19 PORTABLES LOOKING WEST
7/26/21



SCHOOL NO 19 PORTABLES LOOKING SOUTHWEST
7/26/21

SEWARD SCHOOL NO. 19

Seward Street Cor. Magnolia Street

The original building was a two story brick structure having six rooms and was erected in 1869 at a cost of \$9,988.00. In 1876 a one room addition was made at a cost of \$1,335.00. The building was remodeled in 1887, costing \$2,505.00, and again in 1892 when contracts were awarded as follows:

Mason Work	A.B. Lauer	\$1,410.00
Carpenter Work	Louis Webber	1,985.00
Painting	H.J. Sike	351.65
Cut Stone	O'Connor & Co.	170.00
		<u>\$3,916.65</u>

On November 14, 1893 a contract for heating was awarded to Thomas W. Ford for \$1,190.00.

Contracts for a new school were awarded on August 15, 1898 as follows:

Mason Work	P. G. Hauck	\$11,456.00
Carpenter Work	Anthony Link	11,955.00
Cut Stone	Gilbert, Brady & Co.	896.00
Plumbing	R. T. Ford	1,520.00
Heating and Ventilating	Barr & Creelman	3,737.60
Painting	Monroe Painting Co.	711.50
		<u>\$30,276.10</u>

On October 15, 1909 contract for electric wiring in Assembly Hall was awarded to Rochester Electric Contracting Co. for \$98.00


On June 1, 1910 contract for an addition was awarded to Edward Strauchen for \$12,998.00. Contract for electric wiring was awarded to Gaufield-Sweeney Co. for \$1,487.00 on December 27, 1915.

SEWARD SCHOOL NO. 19




(Continued)

Contractor for fireproof room for storage of waste paper and oils was awarded to Geo. B. Garrison for \$1,299.00 on December 19, 1919.

This building is a two story brick structure with slate roof; heated and ventilated by direct and indirect hot water system.



Area of building	17 373 s.f.
" " schoolground	43 743 "
" " playground	29 737 "
" " lot	90 853 "



PUBLIC SCHOOL

Scale 1" = 48'-0"

No 19



SCHOOL NO 20 LOOKING NORTHWEST

7/8/21



SCHOOL NO 20. LOOKING NORTHEAST

7/8/21



SCHOOL NO 20 LOOKING SOUTHWEST

7/8/21

HENRY LOMB SCHOOL NO. 20

Oakman Street near Clinton Avenue, North

The original building was erected in 1870 at a cost of \$4,420.00 and enlarged in 1872 at a cost of \$5,882.00. An addition of 6 rooms was made in 1883 at a cost of \$10,000.00. On June 13, 1887 contracts for another addition were awarded as follows:

Mason Work	John Heveron	\$5,400.00
Cut Stone	John Heveron	500.00
Carpenter Work	Jos. May	5,487.00
Painting	Stephen Streb	349.00
		<u>\$11,736.00</u>

Contract for heating and ventilating was awarded to Smead & Northcott for \$8,700.00 on June 27, 1888.

On July 18, 1892, contracts for an addition were awarded as follows:

Mason Work	John N. Smith	\$2,155.00
Carpenter Work	Keener Bros.	1,309.00
Plumbing	Keener Bros.	36.00
Cut Stone	Brayer & Fullerman	285.00
Painting	M. T. Knapp	104.00
Heating and Ventilating	T. C. Northcott	725.00
		<u>\$4,614.00</u>

Contracts for another addition were awarded August 3, 1896 as follows:

Mason Work	J.C. Geminder	\$ 718.50
Carpenter Work	Anthony Link	310.00
Cut Stone	E. L. Oliver	49.80
Painting	J. G. Simmons	54.00
Plumbing	Shaughnessy & Connolly	464.99
Heating	F. B. Callister	84.00
		<u>\$1,681.29</u>

HENRY LOMB SCHOOL NO. 20


(Continued)

On July 5, 1907 contract for building new toilet rooms was awarded to Caldwell Bros. for \$4,160.00.

Contracts for a new building were awarded on April 3, 1911 as follows:

Mason Work	A. Friederich & Sons Co.	\$77,777.00
Carpenter Work	Fred Gleason	30,632.40
Plumbing, Heating and Ventilating	Howe & Bassett	25,739.00
Electrical Work	Rochester Electric Contracting Co.	2,935.00
		<u>\$137,083.40</u>

This building is a three story brick fireproof structure with slag roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in the rooms under hand control.



Area of building	19 544 s.f.
• schoolground	7 128 "
• playground	14 848 "
• lot	41 520 "



SCHOOL NO 21 - LOOKING SOUTHWEST

6/21/21



SCHOOL NO 21 LOOKING NORTHWEST

6/21/21



SCHOOL NO 21 LOOKING SOUTHWEST

6/21/21

JONATHAN CHILD SCHOOL NO. 21

Colvin Street near Jay Street.

In 1873 school was held in a wooden building at the corner of Jay and Whitney Streets. A lot was purchased and a wooden building erected at a cost of \$1,916.00.

A new building was erected in 1880 at a cost of \$10,000.00, (which included land and building).

On July 19, 1893 contracts for a four room addition were awarded as follows:

Mason Work	Stallman Bros.	\$4,215.00
Carpenter Work	Chas. Hetzler	2,058.00
Cut Stone	Lauer & Hageman	393.00
Painting	B. McSteen	203.00
Plumbing	Chas. Hetzler	78.00
		<u>\$7,947.00</u>

Heating contract was awarded to Frank B. Callister for \$408.50 on August 5, 1895.

Contracts for a new building were awarded on October 26, 1912 as follows:


Mason and Carpenter (including plunge, lockers, etc.)	F. H. Rapp	\$81,257.00
Plumbing, Heating and Ventilating	Howe & Bassett	30,040.00
Electrical Work	Rochester Electric Motor Co.	2,195.00
		<u>\$113,492.00</u>

JONATHAN CHILD SCHOOL NO. 21


(Continued)

This building is a three story brick fireproof structure with slag roof; heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.


JAY ST.




Area of present building	12 970	s.f.
• • new addition	3 442	•
• • schoolground	29 103	•
• • playground	55 614	•
• • lot	101 129	•



THIRD FLOOR PLAN



SECOND FLOOR PLAN



FIRST FLOOR PLAN

PUBLIC SCHOOL
Scale 1" = 48'-0"

N^o 21

22



SCHOOL NO 22 LOOKING SOUTHWEST

7/30/21




SCHOOL NO 22 LOOKING SOUTHWEST

7/30/21



SCHOOL NO 22 MAIN ENTRANCE
LOOKING SOUTH

7/30/21



SCHOOL NO 22 LOOKING SOUTHWEST 7/30/21



SCHOOL NO 22 LOOKING SOUTHWEST 7/30/21



SCHOOL NO 22 LOOKING NORTHWEST 7/30/21



SCHOOL NO 22 LOOKING NORTHWEST 7/30/21

LINCOLN SCHOOL NO. 22

Zimbrich Street near Joseph Avenue

The original No. 22 School is located on Joseph Avenue and is now known as the Rochester Shop School, a description of which will follow later.

On September 18, 1916, contracts for a new building were awarded as follows:

Mason and Carpenter Work	R. T. Ford Co.	\$110,617.00
Painting	Monroe Painting Co.	2,635.00
Electrical Work	O'Connell Electric Co.	6,958.00
Vacuum Bleaner	Edward Towe	1,697.50
Automatic Sprinkler	Wright & Alexander Co.	2,797.00
Plumbing	Edward Towe	6,348.00
Heating & Ventilating	Arensmeyer, Warnock & Zahrdt	35,310.00
Roofing	Flesch & Schmitt	10,602.00
Cut Stone	Buffalo Litholite Co.	11,751.00
		<u>\$188,715.50</u>

Plus the following amounts granted the contractors under the Walters law on account of unusual conditions brought about by the World War:

Mason and Carpenter Work	R. T. Ford Co.	\$32,398.00
Painting	Monroe Painting Co.	1,870.54
Electrical Work	O'Connell Electric Co.	5,713.93
Vacuum Cleaner	Edward Towe	51.00
Plumbing	Edward Towe	1,989.69
Heating and Ventilating	Arensmeyer, Warnock & Zahrdt	8,355.54
Roofing	Flesch & Schmitt	1,857.85
		<u>\$ 52,236.55</u>

LINCOLN SCHOOL NO. 22


(Continued)

This building is a two story and basement brick structure with slag roof; heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.

JOSEPH AV.


ZIMBRICH ST.

LEO ST.




SCHOOL NO. 22.


Area building	31 130 s. f.
• schoolground	<u>29 519</u>
• lot	60 649



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN



PUBLIC SCHOOL

No 22


Scale 1" = 64'-0"



SCHOOL NO 23 LOOKING EAST AT MAIN
ENTRANCE 8/4/21



SCHOOL NO 23 LOOKING SOUTH SHOWING
PORTABLES 8/4/21



SCHOOL NO 23 LOOKING NORTH SHOWING
PORTABLES 8/4/21



SCHOOL NO 23 LOOKING WEST
SHOWING PORTABLES 8/4/21

FRANCIS PARKER SCHOOL NO. 23

Barrington Street corner Thayer Street

The original building was erected in 1883 at a cost of \$5,000.00. Contracts for an addition were awarded July 18, 1892 as follows:

Mason Work	A. B. Lauer	\$1,525.00
Cut Stone	Brayer & Fullerman	168.00
Carpenter Work	Keener Bros.	1,830.00
Plumbing	Keener Bros.	30.00
Painting	M. T. Knapp	160.00
		<u>\$3,713.00</u>

On June 25, 1894 contracts for another addition were awarded as follows:

Mason Work	Schreiner Bros.	\$280.00
Carpenter Work	H. Tosch	225.00
Painting	W. R. Foristal	34.00
Plumbing	Barr & Creelman	407.72
		<u>\$946.72</u>

Contracts for the erection of a new school building were awarded April 18, 1902 as follows:

Mason Work	P.G. Hauck	\$26,128.00
Carpenter Work	F.J. Sauer	18,535.00
Iron Work	F.L. Hughes & Co.	1,625.00
Painting	M.T. Knapp	840.00
Plumbing	R.T. Ford	2,243.00
Heating and Ventilating	Barr & Creelman	8,461.00
		<u>\$57,832.00</u>

FRANCIS PARKER SCHOOL NO. 23

(Continued)

This entire building, except a few rooms and the outside walls, was destroyed by fire in November 1905 and was re-built during 1905 and 1906. This work was done by the following contractors and at the following costs:


Mason Work	P. G. Hauck	\$7,169.53
Carpenter Work	F. J. Sauer	17,208.41
Electrical Work	F. H. Evert	466.82
Roofing	The John Siddons Co.	5,532.00
Plumbing	R. T. Ford	1,674.86
Cut Stone	Geo. E. Noeth Co.	634.38
Painting	M. T. Knapp	1,571.13
Stained Glass	Pike Stained Glass Co.	50.00
		<hr/> \$34,307.13

On October 15, 1909 the Rochester Electric Contracting Co. were awarded contract for electric wiring in Assembly Hall for \$86.00. Contract for a fire alarm system was awarded to the American Telephone Fire Alarm Co. for \$701.50 on February 1, 1915. The O'Connell Electric Co. was awarded contract for electric wiring in remainder of the building for \$1,798.23 on December 27, 1915.

This building is a two story brick structure with slate and tin roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in the rooms under hand control.


BARRINGTON ST.

EDGERTON ST.




MILBURN ST.


Area of building	16 424 s.f.
" " schoolground	<u>69 895</u> "
" " lot	86 319 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

Scale 1" = 48'-0"

N^o 23



NEW SCHOOL NO. 24
LOOKING SOUTHEAST

6/9/21.



NEW SCHOOL NO. 24
LOOKING WEST

6/9/21.



NEW SCHOOL NO. 24
LOOKING NORTHWEST

6/9/21



OLD AND NEW SCHOOL NO. 24
LOOKING SOUTH

6/9/21

ELLWANGER & BARRY SCHOOL NO. 24

South Meigs Street corner Linden Street

The original School No. 24 is situated on the Northeast corner of Meigs and Linden Streets and will be described later.

Contracts for a new safety first school were awarded May 20, 1913 as follows:


Mason and		
Carpenter Work	R. T. Ford	\$55,391.00
Heating and		
Ventilating	R. T. Ford	27,255.00
Plumbing	R. T. Ford	8,024.35
Electrical Work	Rochester Gas Appliance Co.	2,536.00
		<u>\$93,206.35</u>

On August 7, 1919 contract for fireproof room for storage of waste paper and oils was awarded to John Rankin for \$1,689.00.


This building is situated on the Southeast corner of Meigs and Linden Streets and is a one story brick and hollow tile stuccoed, structure with slag roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in the rooms under hand control.

MEIGS ST.

BENTON ST.



LINDEN ST.




CRAWFORD ST.

OLD SCHOOL NO. 24.

Area of building	7 687 s.f.
" " schoolground	<u>28 215</u> "
" " lot	35 902 "

NEW SCHOOL NO. 24.

Area of building	33 252 s.f.
" " schoolground	<u>46 918</u> "
" " lot	80 170 "



PUBLIC SCHOOL

Scale 1" = 32'-0"

Nº 24



SCHOOL NO 25 LOOKING WEST

8/16/21



SCHOOL NO 25 LOOKING NORTHWEST

8/16/21



SCHOOL NO 25 - LOOKING NORTHEAST

8/16/21



SCHOOL NO 25 - LOOKING SOUTH

8/16/21

NATHANIEL HAWTHORNE SCHOOL NO. 25

North Goodman Street corner Bay Street

The original School No. 25 is situated on the Northeast corner of Goodman Street & Bay Street and is now known as the Boys' Prevocational School. This will be described later.

Contracts for a new safety first school were awarded May 15, 1914 as follows:


Mason Work	P. G. Hauck	\$22, 106.00
Carpenter Work	A. W. Hopeman & Sons Co.	32, 222.00
Heating and Ventilating	Edward Towe	23, 567.00
Plumbing	R. T. Ford Co.	3, 999.00
Electrical Work	Rochester Electric Contracting Co.	2, 350.00
		<u>\$84, 244.00</u>

Contract for cement steps and sidewalks was awarded to P. G. Hauck for \$861.00 on July 19, 1915.

On May 7, 1917 contracts for a six room addition were awarded as follows:


Mason Work	E. Strauchen	\$9,104.00
Carpenter Work	Fred Gleason	10,168.00
Heating and Ventilating	Arensmeyer, Warnock & Zahrndt	1,606.00
Plumbing	Howe & Bassett	1,270.00
Electrical Work	Laube Electric Construction Co.	592.00
Roofing	Morrey & Cole	2,890.00
		<u>\$25,630.00</u>

This building is situated on the Northwest corner of North Goodman and Bay Streets and is a one and two story brick and hollow tile, stuccoed, structure with slag roof; heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.




BOYS PREVOCATIONAL SCHOOL
 Area of building 5 062 s.f.
 " " schoolground 21 919 "
 " " lot 26 981 "

SCHOOL No. 25.
 Area of building 28 173 s.f.
 " " schoolground 52 636 "
 " " lot 80 809 "



SECOND FLOOR PLAN




FIRST FLOOR PLAN

PUBLIC SCHOOL


Scale 1" = 48'-0"

No 25


BPS



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BOYS PREVOCATIONAL SCHOOL

Scale 1" = 32'-0"



SCHOOL NO 26 FRONT - LOOKING SOUTHWEST 7/21/21



SCHOOL NO 26 FRONT - LOOKING SOUTHEAST 7/21/21



SCHOOL NO 26 - KINDERGARTEN ENTRANCE
LOOKING SOUTHWEST 7/21/21



SCHOOL NO 26 - LOOKING NORTHEAST SHOWING SITE
FOR ADDITION - HENRY AND ALPHONSE STREETS 6/21/21

SILVANUS A. ELLIS SCHOOL NO. 26

Bernard Street


The original School No. 26 is now known as Washington Junior High School and will be described later.


Contracts for a new school were awarded July 31, 1914 as follows:

Mason Work &	R. T. Ford Co.	\$109,900.00
Carpenter Work	Arensmeyer, Warnock	
Heating and	& Zahrdt	23,000.00
Ventilating	Barr & Creelman	4,596.00
Plumbing	Warder, Clark & Chaplin	
Electrical Work	Electric Co.	4,174.00
		<u>\$141,670.00</u>


On July 21, 1919 contract for laying cement walks was awarded to P. G. Hauck for \$1,672.00.

This building is a two story brick structure with slag roof; heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.






SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

N^o 26


Scale 1" = 64'-0"



SCHOOL NO 27 LOOKING NORTHWEST 8/5/21



SCHOOL NO 27 LOOKING SOUTHWEST 8/5/21



SCHOOL NO 27 LOOKING SOUTHEAST



SCHOOL NO 27 LOOKING NORTHEAST SHOWING HOUSES ON NIAGARA STREET 8/5/21

SUSAN B. ANTHONY SCHOOL NO. 27

Central Park. cor. First Street.

The original building was erected in 1883 at a cost of \$5,000.00, and in 1884 contracts for an addition of two rooms were awarded as follows:

Mason Work	Louis Weber	\$1,820.00
Carpenter Work	Chas. Horn	2,025.00
		<u>\$3,845.00</u>

A second story was added in 1886, when contracts were awarded as follows:

Mason Work	John Karweick	\$2,536.80
Cut Stone	F. C. Lauer	95.00
Carpenter Work and Painting	Chas. L. Horn	3,306.00
		<u>\$5,937.80</u>


Contracts for a new building were awarded April 16, 1900 as follows:

Mason Work	Ed. Strauchen	\$15,598.00
Carpenter Work	Anthony Link	17,365.00
Iron & Steel Work	Roch. Bridge & Iron Works	1,579.00
Plumbing	Jas. Reynolds	1,735.00
Heating & Ventilating	Frank H. Falls	8,031.00
Painting	Monroe House Painting Co.	836.50
		<u>\$45,144.50</u>

On July 2, 1906 contract for a four room addition was awarded to Anthony Link for \$9,538.00.

Contract for electric wiring was awarded February 19, 1915 to R. T. Huber Co. for \$1,500.00.


NIAGARA ST.




FIRST ST.

CENTRAL PARK


Area of buildings	37 295 s.f.
" " schoolground	<u>29 905 s.f.</u>
" " lot	67 200 s.f.



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

Scale - 1" = 64'-0"

Nº 27



SCHOOL NO 28 LOOKING NORTH FROM FRONT 7/22/21



SCHOOL NO 28 LOOKING WEST FROM REAR 7/22/21

HENDRIK HUDSON SCHOOL NO. 28

Humbolt Street

Contracts for a new safety first school were
awarded May 8, 1914 as follows:

Mason Work	A. Friederich & Sons	\$23,056.00
Carpenter Work	Homer Knapp	34,485.00
Heating and Ventilating	Wright & Alexander	21,409.00
Plumbing	Wright & Alexander	4,176.00
Electrical Work	Fish & Horton Co.	2,433.00
		<u>\$85,559.00</u>


On May 1, 1916 contracts for an addition were

awarded as follows:


Mason Work	Ed. Strauchen	\$6,627.00
Carpenter Work	Wm. F. Maas & Son	7,386.00
Plumbing	R. T. Ford Co.	940.00
Heating and Ventilating	R. T. Ford Co.	1,273.00
Electrical Work	T. R. Humber Co.	693.00
Roofing	Knowles & Peck	1,742.00
		<u>\$18,661.00</u>

Contract for fireproof room for storage of waste
paper and oils and for laying cement walks was awarded to
John Rankin September 5, 1919 for \$2,390.00.

This building is a one and two story brick and
hollow tile, stuccoed, structure with slag roof; heated and v
ventilated by fan system and direct radiation in rooms, under
automatic temperature control.



Area building	33 730 s. f.
" schoolground	182 520 "
" lot	216 250 "



PUBLIC SCHOOL

Scale 1" = 48'-0"

N^o 28



SCHOOL NO 29 LOOKING NORTH

6/21/21



SCHOOL NO 29 LOOKING SOUTH FROM ASSEMBLY HALL ENTRANCE

6/21/21

JAMES WHITCOMB RILEY SCHOOL NO. 29

Moran Street near Genesee Street

The original building was erected in 1884 when contracts were awarded as follows:

Mason Work	Chas. R. Pratt	\$4,085.00
Carpenter Work	Thos. Salter	3,000.00
		<u>\$7,085.00</u>

This building was enlarged in 1890, the contracts being awarded as follows:

Mason Work	A. E. Lauer & Co.	\$4,597.00
Cut Stone	Wall & Gledhill	290.00
Carpenter Work	Walters & Ziegler	4,581.00
Painting	Walters & Ziegler	200.00
Heating	Fuller, Warren Co.	2,200.00
		<u>\$11,868.00</u>

On July 1, 1895 contracts for an addition were awarded as follows:

Mason Work	John Karweick	\$2,699.50
Carpenter Work	William Doody	2,545.00
Cut Stone	Stallman Bros.	158.00
Heating and Ventilating	T. C. Northcott	1,200.00
Painting	G. W. Webb	395.00
Plumbing	Maier & Glasgow	55.00
		<u>\$7,052.50</u>

Contracts for another addition were awarded August 3, 1896 as follows:

Mason Work	F. P. Stallman	\$2,347.00
Carpenter Work	T. Salter	2,070.00
Plumbing	Maier & Glasgow	91.00
Cut Stone	Lauer & Hageman	341.00
Painting	J. C. Simmons	265.00
Heating and Ventilating	T. C. Northcott	510.00
		<u>\$5,624.00</u>

JAMES WHITCOMB RILEY SCHOOL NO. 29

(Continued)

On April 3, 1900 contracts for an addition were awarded as follows:


Mason Work	Beale & Beisheim	\$5,398.96
Carpenter Work	Anthony Link	5,869.00
Steel Work	Reoh. Bridge & Iron Works	374.00
Painting	A. H. Hawkin & Son	345.00
Plumbing	R. T. Ford	1,252.10
Heating	R. T. Ford	<u>7,867.00</u>
		\$21,106.06

Contract for the building of an assembly hall was awarded August '10, 1909 to F. H. Rapp & Co. for \$9,549.00.

- This building was damaged by fire in 1913 which made considerable repairs necessary.

On March 19, 1915 contract for electric wiring was awarded to T. R. Huber Co. for \$1,485.00. Contract for taking down tower and altering the front to get a fireproof stair tower was awarded to Leo J. Held for \$4,699.00.

This building is a two story brick structure with slate and gravel roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in the rooms under hand control.



Area of building	19 094 s.f.
" " schoolground	15 556 "
" " lot	34 650 "



SCHOOL NO 30 - LOOKING NORTHWEST

6/30/21

GENERAL E. S. OTIS SCHOOL NO. 30
Otis Street corner Asab Street

The original building was erected in 1884 when contracts were awarded as follows:

Mason Work	J.M. Lauer & co.	\$4,085.00
Carpenter Work	Thos. W. Finucane	2,000.00
		<u>\$7,085.00</u>

A second story wing was added in 1885 at a cost of \$1,130.00

Contracts for enlarging the school were awarded in 1890 as follows:

Mason Work	A.E. Lauer & Co.	\$4,767.00
Carpenter Work	J.F. Montgomery & Sons	3,275.00
Cut Stone	O'Connor & Co.	245.00
Heating	T. C. Northcott	1,180.00
Painting	Jas. C. Simmons	329.00
		<u>\$9,806.00</u>

On April 3, 1900 the contracts for an addition were awarded as follows:

Mason Work	Geo B. Garrison	\$6,490.00
Carpenter Work	Thomas Salter	7,097.00
Steel Work	Reich, Bridge & Iron Works	557.00
Painting	Monroe House Painting Co.	365.00
Plumbing	James Reynolds	1,657.00
Heating & Ventilating	R.T. Ford	6,211.00
		<u>\$22,377.00</u>

Contract for Electric wiring was awarded October 13, 1909 to Wheeler-Green Co. for \$1,497.00

GENERAL E. S. OTIS SCHOOL NO. 30
(Continued)

On March 25, 1918, contracts for the addition of a kindergarten, four class rooms, assembly hall and boiler room were awarded as follows:


Mason Work	A. Friederich & Sons Co.	\$48,289.00
Carpenter Work	Fred Gleason	24,505.39
Heating & Ventilating	Arensmeyer, Wernock & Zahrdt	15,374.00
Plumbing	Martin Utz	3,335.00
Electrical Work	Huber Electric Co.	4,663.50
Roofing	Wm. J. Meyer Co.	4,888.00
Vacuum Cleaning	Wheeler-Green Electric Co.	1,867.50
Painting	Monroe Painting Co.	2,390.00
		<hr/> \$108,312.39

This building is a two story brick structure with built-up asbestos, slate and tin roof; heated and ventilated by fan system and direct radiation in rooms, under automatic temperature control.


AAB ST.

CHACE ST.


OTIS ST.




Area of building	19 917 s.f.
" " schoolground	10 683 "
" " lot	30 600 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN


PUBLIC SCHOOL
Scale 1" = 48'-0"


No 30





SCHOOL NO. 31 (OLD)

6/1/21.





SECOND FLOOR PLAN



FIRST FLOOR PLAN

PUBLIC SCHOOL NO. 31 (OLD)

Scale 1" = 48' 0"

• Fire Extinguishers



SCHOOL NO. 31 (NEW)

6/1/21.



SCHOOL NO. 31 (NEW)

6/1/21.



SCHOOL NO. 31 (NEW)

6/1/21.

HAMILTON SCHOOL NO. 31

University Avenue corner Merriman Street

The first session of No. 31 School was held in 1865 in a building at the corner of Bacon Street and University Avenue.


The present building was erected in 1887 when contracts for the new school were awarded as follows:

Mason Work	C. R. Pratt & Co.	\$8,425.00
Cut Stone	F. C. Lauer & Co.	1,053.22
Carpenter Work	W. F. Devendorf	5,675.00
Heating and Ventilating	Smead & Northcott	1,700.00
Plumbing	Smead & Northcott	250.00
Painting	Geo. H. Nicholson	480.00
		<u>\$17,583.22</u>


In 1895 an addition was made to the school, the contract being awarded as follows:

Mason Work	Joseph Schnopp	\$2,873.00
Cut Stone	Gilbert Brady	315.00
Carpenter Work	Anthony Link	3,630.00
Heating and Ventilating	T. C. Northcott	1,187.00
Plumbing	Shaughnessy & Connolly	314.00
Painting	S. Street	195.00
		<u>\$8,514.00</u>

This building is a two story brick structure with slate roof; heated by hot air furnaces.



Area of building	23 749 s. f.
" " Schoolground	<u>16 511</u> "
" " lot	40 260 "



PUBLIC SCHOOL

Scale 1" = 48'-0"

Nº 31



SCHOOL NO 32 FRONT
LOOKING NORTHWEST 7/26/21



SCHOOL NO 32 FRONT-LOOKING
NORTH 7/26/21



SCHOOL NO 32 REAR-LOOKING SOUTHWEST 6/26/21

PLYMOUTH SCHOOL NO. 32

Barlett Street corner Plymouth Avenue


The original and present building was erected in 1889 when contracts for an eight room school were awarded as follows:

Mason Work	J.J. Heveron & Co.	\$8,678.00
Cut Stone	O'Connor & Co.	1,018.00
Carpenter Work	Jno. Karweick	6,100.00
Heating & Ventilating	Smead & Northcott	2,275.00
Painting	Stephen & Streb	375.00
		<u>\$ 18,446.00</u>




On August 20, 1912 contracts for new toilets was awarded to H. G. Hammon & Son for \$2,192.00.

Contracts for electric wiring was awarded to Huber Electric Co. March 13, 1917 for \$1,027.33.

This building is a two story brick structure with slate and tin roof: heated by hot air furnaces.



Area of building	6 604 s.f.
" " schoolground	14 024 "
" " lot	20 628 "



PUBLIC SCHOOL

N^o 32

Scale 1" = 32'-0"



SCHOOL NO 33 LOOKING NORTHEAST

7/6/21



SCHOOL NO 33 - LOOKING NORTHEAST

7/6/21

AUDUBON SCHOOL NO. 33

Grand Avenue near Oswego Street

The original building was erected in 1891, the contract being awarded as follows:

Mason Work	John R. Strauchen	\$7,533.00
Carpenter Work	John A. DeBlawe	5,740.00
Cut Stone	Wall & Gledhill	875.00
Heating & Ventilating	Smead & Northcott	2,275.00
Plumbing	Jos. P. Dailey	175.00
Painting	J. R. Brady	250.00
		<u>\$ 16,848.00</u>

On July 6, 1891 contract for finishing the school was awarded to Philip Blaesi for \$1,519.00.

Contracts for an addition were awarded August 3, 1896 as follows:

Mason Work	Jos. Schnopp	\$1,970.00
Cut Stone	E. L. Oliver	282.15
Carpenter Work	Anthony Link	1,498.00
Heating & Ventilating	T. G. Northcott	510.00
Plumbing	J. Rice	92.87
Painting	R. Forrestal	105.00
		<u>\$4,558.02</u>

On October 16, 1899 contracts for an addition were awarded as follows:

Mason Work	Jos. Fleckenstein	\$5,971.00
Cut Stone	Brayer & Albaugh	685.59
Carpenter Work	John Keener & Son	4,855.00
Heating & Ventilating	Northcott Warming & Ventilating Co.	1,465.00
Plumbing	Fladd & Bay	421.65
Painting	A. H. Hawken & Son	185.00
		<u>\$13,583.24</u>

AUDUBON SCHOOL NO. 33



(Continued)

Contract for electric wiring was awarded to the Rochester Electric Motor Co. for \$900.00 on November 21, 1910. On September 6, 1911 contract for new toilets was awarded to Anthony Link for \$5,000.00. Contract for erecting a new boiler room and installing a new system of heating and ventilating was awarded to Towe & Devendorf on June 10, 1912 for \$22,300.00.

On April 12, 1918 contract for electric wiring and fixtures was awarded to Huber Electric Co. for \$1,684.00.

Contract for fireproof room for the storage of waste paper and oils was awarded to John Rankin October 14, 1919 for \$1,595.00.

This building is a two story brick structure with slate roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.



GRAND AV.


NEW ADDITION

SCHOOL NO. 33.


New Cool Room
Addition

Area present building	13 216 s.f.
" new additions	13 147 "
" schoolground	26 797 "
" lot	53 160 "


CHAMBERLAIN ST.




SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN



PUBLIC SCHOOL

Scale-1"=48'-0"

N^o 33



SCHOOL NO 34 LOOKING NORTH
6/30/21



SCHOOL NO 34 LOOKING NORTHEAST

6/30/21



SCHOOL NO 34 LOOKING SOUTHWEST

6/30/21

LEXINGTON SCHOOL NO. 34

Lexington Avenue

The original building was erected in 1890 when contracts were awarded as follows:

Mason Work	John Heveron	\$9,750.00
Cut Stone	Gilbert Brady & Co.	598.00
Carpenter Work	J. F. Montgomery & Son	5,100.00
Stone Steps	R. H. Cutis	99.00
Heating & Ventilating	T. C. Northcott	1,650.00
Painting	M. T. Knapp	215.00
		<u>\$17,412.00</u>

An addition of four rooms was made in 1891 the contracts being awarded as follows:

Mason Work	H. G. Larzelere	\$ 221.00
Carpenter Work	H. G. Larzelere	1,393.00
Plumbing	H. G. Larzelere	25.00
Heating & Ventilating	T. C. Northcott	1,000.00
Painting	H. J. Sike	157.00
		<u>\$2,776.00</u>


On July 11, 1912 contract for new toilet rooms was awarded to Dunning & Glasser for \$7,438.00.

This building is a two story brick structure with slate roof; heated by hot air furnaces.

40




HOLMES ST.




LEXINGTON AV.


Area of building	5 492 s.f.
" " schoolground	16 108 "
" " playground	<u>22 400</u> "
" " lot	44 000 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN



PUBLIC SCHOOL

Scale 1" = 32'-0"

N^o 34

Exit =



SCHOOL NO. 35
FRONT VIEW

6/10/21



SCHOOL NO. 35
LOOKING EAST

6/10/21



SCHOOL NO. 35
SHOWING DRIVEWAY LEASED TO MR. SAUNDERS

6/10/21

PINNACLE SCHOOL NO. 35

Field Street corner Kusse Street

Contracts for the original building were awarded
February 18, 1895 as follows:

Mason Work	Joseph Schnopp	\$3,595.00
Carpenter Work	F. J. Sauer	2,630.00
Cut Stone	E. L. & H. T. Oliver	387.75
Painting	F. J. Sauer	170.00
		<u>\$6,782.75</u>

On August 17, 1896 contracts for an addition were
awarded as follows:

Mason Work	H. Stallman & Sons	\$ 352.80
Carpenter Work	F. H. Rapp	809.00
Heating & Ventilating	R. T. Ford	1,096.00
Painting	Kinney Bros.	90.00
		<u>\$2,347.80</u>

Contracts for another addition were awarded April 3,
1900 as follows:

Mason Work	P. G. Hauck	\$3,559.00
Carpenter Work	Thos. Salter	3,000.00
Steel Work	Roch. Bridge & Iron Works	233.00
Plumbing	W. G. Reid & Son	880.00
Heating	Howe & Bassett	1,644.80
Painting	Stephen Stimb	275.00
		<u>\$9,591.80</u>

PINNACLE SCHOOL NO. 35



(Continued)

On August 20, 1912 contracts for a four room addition were awarded as follows:

Mason Work	P. G. Hauck	\$8,693.00
Carpenter Work	Homer Knapp	8,256.00
Plumbing	R. T. Ford Co.	1,500.00
Heating, Ventilating & Electrical	R. T. Ford Co.	2,180.00
		<u>\$20,629.00</u>


Contract for electric wiring was awarded December 27, 1915 to E. C. Sykes & Co. for \$785.00.

This building is a two story brick structure with tin roof; heated by direct and indirect steam.




LABURNUM CRESCENT


Area of present building	9 736 s.f.
" " new addition	9 090 "
" " schoolground	<u>26 598</u> "
" " lot	45 424 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

Scale 1" = 48'-0"

N^o 35



SCHOOL NO. 36 LOOKING SOUTHWEST

7/8/21



SCHOOL NO 36 LOOKING SOUTHWEST

7/8/21



SCHOOL NO 36 LOOKING NORTHWEST

7/8/21



SCHOOL NO 36. SHOWING FLAG POLE BASE BROKEN BY LIGHTNING LAST NIGHT. JANITOR STANDS IN FOREGROUND

HENRY W. LONGFELLOW SCHOOL NO. 36

Carter Street corner Bernard Street

Contracts for the original building were awarded
August 1, 1898 as follows:

Mason Work	P. G. Hauck	\$4,628.00
Cut Stone	W. F. Fuhrmann	842.00
Carpenter Work	Philip Enders	4,800.00
Plumbing	R. T. Ford	550.00
Heating	R. T. Ford	1,050.00
Painting	A. W. Hawkin	295.00
		<u>\$12,165.00</u>

On November 23, 1898 contracts for a two room
addition were awarded as follows:

Mason Work	Fred Christ	\$135.00
Carpenter Work	Philip Enders	650.00
Gas Fitting	R. T. Ford	221.00
Heating	R. T. Ford	362.00
Painting	A. N. Hawken & Son	55.00
		<u>\$1,423.00</u>

Contracts for an addition of four rooms and an
assembly hall were awarded as follows on March 22, 1907:

Mason Work	G. G. Kircher	\$10,800.00
Carpenter Work & Painting	Homer Knapp	10,865.46
Plumbing, Heating & Ventilating	R. T. Ford	5,230.00
		<u>\$26,895.46</u>

On October 13, 1909 contract for electric wiring was
awarded to O'Connell Electric Co. for \$1,070.00.

HENRY W. LONGFELLOW SCHOOL NO. 36

(Continued)

Contracts for a four room addition were awarded
August 3, 1910 as follows:

Mason Work	Edward Staruchen	\$10,217.00
Carpenter Work	Anthony Link	14,557.00
Plumbing, heating & Ventilating	Towe & Devendorf	7,889.00
		<u>\$ 32,663.00</u>

On January 6, 1913 contracts for a five room
addition were awarded as follows:


Mason Work	P. G. Hauck	\$7,528.00
Carpenter Work	Doyle & Smith	7,055.00
Heating, Ventilating & Plumbing	Barr & Creelman	4,410.00
Electrical Work	Wheeler-Green Electric Co.	376.00
		<u>\$19,369.00</u>

This building is a two story brick structure with
slate, tile and gravel roof; heated and ventilated by fan
system with air under automatic temperature control from each
room and direct radiation in the rooms under hand control.




ST. JACOB ST.

CARTER ST.

BERNARD ST.



Area of building	20 612 s.f.
" " schoolground	17 764 "
" " playground	41 232 "
" " lot	79 608 "



PUBLIC SCHOOL

Scale 1"=48'-0"

N^o 36

Exit=◇

LEWIS H. MORGAN SCHOOL NO. 37

Post Avenue corner Congress Avenue

Contracts for a new safety first school were awarded
February 21, 1916 as follows:


Mason Work	Curran & Swartout	\$35,000.00
Carpenter Work	Fred Gleason	27,205.00
Cut Stone	Consolidated Cut Stone Co.	2,709.00
Heating & Ventilating	W. F. Devendorf	23,843.00
Plumbing	Wright & Alexander	4,400.00
Electrical Work	Wheeler-Green Electric Co.	2,783.00
Vacuum Cleaner	Edward Towe	1,129.00
Finished Floors	Fred Gleason	2,901.00
Roofing	Wm. J. Meyer Co.	5,880.00
		<u>\$105,850.00</u>

On June 20, 1919 contracts for an addition were
awarded as follows:

Mason Work	Gorsline & Swan Con- struction Co.	\$20,299.00
Carpenter Work	Fred Gleason	17,397.00
Heating & Ventilating	Barr & Creelman	3,732.00
Plumbing	Wright & Alexander	2,541.00
Electrical Work	Wheeler-Green Electric Co.	1,537.00
Roofing & Metal Work	Flesch & Schmitt	3,147.00
		<u>\$48,653.00</u>

This building is a one and two story brick and
hollow tile structure with built-up asbestos roof; heated and
ventilated by fan system and direct radiation in rooms, under
automatic temperature control.

36



Area of building	38 891 s.f.
" " schoolground	92 149 "
" " lot	131 040 "




SCHOOL NO 38 - LOOKING NORTH ^{8/15/21}






SCHOOL NO 38 - LOOKING NORTHEAST ^{8/15/21}



SCHOOL NO 38 - LOOKING SOUTHWEST ^{8/15/21}



Area of School No. 38	6 238 s. f.
" " Charlotte High	4 069 "
" " schoolground	<u>39 837 "</u>
" " lot	50 144 "



PUBLIC SCHOOL

Scale 1" = 48'-0"

N^o 38




SCHOOL NO 38 ANNEX - LOOKING EAST 8/15/21




SCHOOL NO 38 ANNEX - LOOKING WEST 8/15/21




SCHOOL NO 38 ANNEX - LOOKING SOUTHWEST
SHOWING DWELLING 8/15/21




Area of building	1 775 s.f.
" " schoolground	12 225 "
" " lot	14 000 "




SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN



N^o 38 ANNEX
Scale 1" = 16'-0"



SCHOOL NO 39 - SHOWING YARD
8/16/21




SCHOOL NO 39 - LOOKING NORTHEAST 8/16/21



SCHOOL NO 39 - LOOKING WEST 8/16/21


(25)

N. GOODMAN ST.





TRAVER
CIRCLE

Area of building	1 144 s.f.
" " schoolground	4 756 "
" " lot	5 900 "




SECOND FLOOR PLAN



FIRST FLOOR PLAN

PUBLIC SCHOOL
scale 1" = 16'-0"

Nº 39




Area of building	s.f.
" " schoolground	"
" " lot	140 840 "




SCHOOL NO. 40


6/7/21.




Area of buildings	6 148 s.f.
" " schoolground	<u>43 852 "</u>
" " lot	50 000 "




THIRD FLOOR PLAN




SECOND FLOOR PLAN



FIRST FLOOR PLAN




BASEMENT FLOOR PLAN



PUBLIC SCHOOL
Scale 1" = 32'-0"

Nº 40

NEW
40



Area of building s.f.

" " schoolground "

" " lot 247 800 "



SCHOOL NO. 41

6/1/21



SCHOOL NO. 41

6/7/21

DEWEY AV.

(41)

193.85'

Playground

500'

954.16'

821.82'

Area of building	16 178 s. f.
• • schoolground	172 795 •
• • lot	188 973 •




SCHOOL
No. 41.

LEWISTON AV.

DAYTON ST.

1"=100'



PUBLIC SCHOOL

Scale 1" = 48'-0"


N^o 41



SCHOOL NO 42 - LOOKING SOUTH EAST ^{8/15/21}




SCHOOL NO 42 LOOKING WEST ^{8/15/21}





LAKE AV.

STONE RD.

Area of building	5047 s. f.
" " schoolground	46 509 "
" " lot	51 556 "



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

Scale 1" = 32'-0"

Nº 42



SCHOOL NO. 43
SHOWING PORTABLE AND EXCAVATION FOR SEWER 5/27/VI.
LOOKING SOUTHWEST




SCHOOL NO. 43 5/27/VI.
SHOWING EXCAVATION AND FOUNDATION WALLS FOR ADDITION
LOOKING NORTHEAST




GEO. L. SWAN
CONTRACTOR - SCHOOL NO. 43 5/27/VI


42




Area of present building	5 012 s.f.
• • new addition	29 034 •
• • schoolground	<u>86 487 •</u>
• • lot (inc. widening)	120 533 •




SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN




PUBLIC SCHOOL

Scale 1" = 32'-0"

Nº 43


STANTON ST.

FARRAGUT ST.




CHILI AV.


Area of building	6 481 s. f.
• • schoolground	<u>51 071 •</u>
• • lot	57 552 •



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

PUBLIC SCHOOL

Scale 1" = 24'-0"

Nº 44

CON.S



CONTINUATION SCHOOL 838 SMITH ST LOOKING
NORTH WEST 6/21/21

OAS



OPEN AIR SCHOOL LOOKING NORTH 8/4/21



OPEN AIR SCHOOL LOOKING WEST 8/4/21



OPEN AIR SCHOOL LOOKING SOUTH FROM SOUTH BANK
OF THE WIDEWATERS 8/4/21



OPEN AIR SCHOOL LOOKING SOUTH FROM NORTH BANK OF
THE WIDEWATERS 8/4/21



Approximate Location of Blue Line

GARDEN

OPEN AIR
SCHOOL


ROAD

ROAD


To Culver Rd.

Area building	4 337	s. f.
" schoolground	72 462	"
" lot	76 799	"


1" = 50'



SECOND FLOOR PLAN



FIRST FLOOR PLAN




BASEMENT FLOOR PLAN

OPEN AIR SCHOOL

Scale 1" = 48'-0"

RSS



ROCHESTER SHOP SCHOOL - LOOKING
WEST - MAIN ENTRANCE 7/30/21



ROCHESTER SHOP SCHOOL LOOKING SOUTHWEST
7/30/21



ROCHESTER SHOP SCHOOL LOOKING NORTH
7/30/21

ROCHESTER SHOP SCHOOL
(Formerly School No. 22)
Joseph Avenue corner Avenue D.

The original building was erected in 1883 at a cost of \$2,500.00. Contracts for an addition were awarded March 9, 1887 as follows:

Mason Work	John Heveron	\$725.00
Carpenter Work	Sprague & Green	930.75
Painting	Stephen Streb	75.00
Cut Stone	F. C. Lauer & Son	114.00
		<u>\$1,844.75</u>

On July 1, 1889 contracts for an addition of four rooms were awarded as follows:

Mason Work	Stallman Bros.	\$1,297.00
Cut Stone	Wall & Gledhill	210.00
Carpenter Work	Philip Blaesi	2,235.00
Painting	M. T. Knapp	124.00
		<u>\$3,866.00</u>

Contracts for another addition were awarded July 19, 1893 as follows:

Mason Work	Stallman Bros.	\$5,417.00
Carpenter Work	Joseph May	5,339.00
Cut Stone	Brayer & Fuhrman	974.00
Heating & Ventilating	T. C. Northcott	2,695.00
Painting	Stephen Streb	285.00
Plumbing	E. Dumond & Son	99.00
		<u>\$14,809.00</u>

ROCHESTER SHOP SCHOOL

(Continued)

Contract for electric wiring was awarded to Huber Electric Co. for \$3,200.00 on November 6, 1918.


Until November 1918 this school was known as Schhol No. 22, when it became known as the Rochester Shop School upon the completion of new School No. 22.

This building is a two story brick structure with slate and tin roof; heated by hot air furnaces.


NIBROC BOND

AVENUE D


JOSEPH AV.




Area of building	8 027 s.f.
" " schoolground	13 150 "
" " lot	21 177 "



SECOND FLOOR PLAN



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN

ROCHESTER SHOP SCHOOL

Scale 1" = 32'-0"

ENTER

ANNE
EHS



EAST HIGH ANNEX - 302 NORTH GOODMAN ST. 5/25/21.
LOOKING NORTHEAST

EHS




EAST HIGH SCHOOL - FRONT-
LOOKING EAST 8/1/21




EAST HIGH SCHOOL LOOKING WEST 8/1/21




EAST HIGH SCHOOL LOOKING NORTH 8/1/21




Area of building	37 086 s.f.
" " schoolground	95 656 "
" " lot	132 742 "



FIRST FLOOR PLAN



BASEMENT FLOOR PLAN



EAST HIGH SCHOOL

Scale 1" = 48'-0"

EXIT = ◇

EAST HIGH SCHOOL

Alexander Street near Main Street

The original and present building was built in 1901-2 when contracts were awarded as follows:

Structural Steel	Kellog Iron Works	\$13,470.00
Excavation & Foundation Walls	A. Friederich & Sons Co.	12,502.00
Mason Work, Cut Stone Work, Concrete Floors and Fireproofing, Carpenter Work, Interior Woodwork, Plumbing & Gas	Thos. Finucane Co.	175,000.00
Heating & Ventilating	Richard T. Ford	34,996.00
Electric Light Wires	J. C. Sterns & Co.	4,970.00
Telephones	Rudolph Schmitt & Co.	1,495.00
System of Electric Clocks, Bells and Gongs	Fred Frick Clock Co.	1,886.00
Special Fixtures, Laboratory Tables, Etc.	Richard T. Ford	9,299.00
		<u>\$253,618.00</u>

In February 1914 contracts for finishing Manual Training Room, including larger windows and areaway, were awarded as follows:


Mason & Carpenter Work	H. G. Hammon & Son	\$1,590.00
Plumbing	A. J. Heinze	116.00
Electrical Work	Warder, Clark & Chaplin Electric Co.	236.00
		<u>\$1,942.00</u>

On July 31, 1914 contract for Bicycle Room and Store Room was awarded to Wm. F. Meas for \$2,675.00. The Ricker Manufacturing Co. were awarded contract for ash lift December 27, 1915 for \$524.00. Contract for fire escape was awarded to L. J. Held February 21, 1916 for \$1,089.50.


EAST HIGH SCHOOL

(Continued)


This building is a three story and basement fire-proof brick structure with slate, tin and slag roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in the rooms under hand control.



THIRD FLOOR PLAN



SECOND FLOOR PLAN



EAST HIGH SCHOOL

Scale 1" = 48'-0"

WHS



WEST HIGH SCHOOL
LOOKING NORTHWEST

5/28/21.



WEST HIGH SCHOOL
LOOKING SOUTHWEST


5/28/21.

ALDINE ST.

556.74'

MONTGOMERY ST.

610'





610'


GENESEE ST.

ABERDEEN ST.


Area of building	34 524 s.f.
• schoolground	305 902
• lot	340 426



WEST HIGH SCHOOL



THIRD FLOOR PLAN



SECOND FLOOR PLAN



WEST HIGH SCHOOL

Scale 1" = 48'-0"

NEWS



NORTHEAST HIGH SCHOOL SITE - LOOKING NORTHEAST ALONG
NORTON STREET SHOWING CORNER BUILDING

7/12/21



NORTHEAST HIGH SCHOOL SITE - LOOKING NORTH WEST
SHOWING DWELLING EAST OF SCHOOL SITE

7/12/21



NORTHEAST HIGH SCHOOL SITE - LOOKING SOUTH
ALONG HUDSON AVENUE

7/12/21



7/12/21 NORTHEAST HIGH SCHOOL SITE - LOOKING NORTH-
EAST ALONG HUDSON AVENUE SHOWING CORNER BUILDING

(15)

REXFORD ST.

100

716.48'

399.46'

SITE FOR NORTH SIDE
HIGH.

120'

200'

200'

120'

50'

240'

200'

200'

240'

50.1'

180.5'

219.45'

218.64'

180.5'

539.53'

1116.42'

LEFROIS ST.

KILMAR ST.

100'

NORTON ST.

Area of building

- • schoolground
- • lot

691 254 s.f.

1" = 150'

1
vli

WJH



WASHINGTON JUNIOR HIGH SCHOOL - LOOKING SOUTH -
SHOWING 755 - 759 - 763 CLIFFORD AVENUE 7/21/21



WASHINGTON JUNIOR HIGH SCHOOL - LOOKING NORTHEAST
SHOWING LOCATION OF PROPOSED ADDITION 7/21/21



WASHINGTON JUNIOR HIGH SCHOOL - LOOKING EAST
SHOWING SOUTHWEST CORNER 7/21/21



WASHINGTON JUNIOR HIGH SCHOOL SHOP
LOOKING NORTH 7/21/21

WASHINGTON JUNIOR HIGH SCHOOL
(Formerly School No. 26)
Clifford Avenue cor. Thomas Street

The original building was erected in 1879 at a cost of \$6,857.00. In 1883 an addition of six rooms was made at a cost of \$6,300.00. Again in 1890 an addition was made when contracts were awarded as follows:

Mason Work	Chas. L. Horn	\$6,053.00
Carpenter Work	Chas. L. Horn	4,314.00
Cut Stone	O'Connor & Co.	825.00
Heating	T. C. Northcott	1,860.00
Painting	Jas. Simmons	518.00
		<u>\$13,570.00</u>

Contracts for another addition of six rooms were awarded July 11, 1892 as follows:

Mason Work	Louis Webber	\$4,993.00
Carpenter Work	Wm. Baird	3,285.00
Cut Stone	Louis Webber	664.00
Painting	J. N. Smith	250.00
Plumbing	Shaughnessy & Co.	85.88
Heating & Ventilating	T. C. Northcott	1,575.00
		<u>\$10,852.88</u>

On August 3, 1896 contracts for kindergarten were awarded as follows:

Mason Work	Louis Webber	\$3,254.00
Carpenter Work	John Keener & Son	3,705.00
Cut Stone	Brayer & Fuhrman	391.00
Painting	Jas. Simmons	220.00
Heating & Ventilating	T. C. Northcott	665.00
		<u>\$8,235.00</u>

WASHINGTON JUNIOR HIGH SCHOOL

(Continued)

A three room addition was made, contracts being awarded as follows November 23, 1898:

Mason Work	Jos. Schnopp	\$ 75.00
Carpenter Work & Ceiling	H. Horn	1,733.00
Painting	A. Link	115.00
Gas Fitting	E. J. Rice	39.00
Electrical Work	Elwood & Brien	50.00
Heating	Northcott Warming & Ventilating Co.	554.00
		<u>\$2,566.00</u>

In 1908 part of the old building was torn down and the east wing of the new building was built. Contracts were awarded as follows:

Mason Work	Genesee Construction Co.	\$59,427.00
Carpenter Work & Painting	A. W. Hopeman	46,118.00
Plumbing, Heating & Ventilating	Barr & Creelman	28,756.00
		<u>\$134,301.00</u>

The west wing of the new building was built in 1909, contracts being awarded as follows:

Mason, Carpenter, Painting & Electrical Work	A. W. Hopeman & Sons Co.	\$55,800.00
Plumbing, Heating & Ventilating	R. T. Ford Co.	13,987.00
		<u>\$69,787.00</u>

WASHINGTON JUNIOR HIGH SCHOOL

(Continued)


Upon the completion of New School No. 26, this school became known as the Washington Junior High School. The building was altered and new shops were built, for which contracts were awarded as follows:: January 4, 1915:


Mason Work	P. G. Hauck	\$27,793.00
Carpenter Work	W. F. Maas	12,799.00
Plumbing	R. T. Ford	1,773.00
Heating & Ventilating	R. T. Ford	9,869.00
Electrical Work	Fish & Horton Co.	2,169.00
		<u>\$54,403.00</u>

On December 27, 1915 contract for freight elevator was awarded to Otis Elevator Co. for \$1,440.00. Contract for clock system was awarded to E. Howard Clock Co. On July 31, 1916 for \$2,552.00. On November 6, 1916, contract for sprinkler system was awarded to Wright & Alexander for \$4,037.00.



Contract for telephone equipment was awarded to Stromberg-Carlson Telephone Mfg. Co. February 2, 1917 for \$1,133.64.

This building is a two story and basement brick structure with slag and tin roof; heated and ventilated by fan system with air under automatic temperature control from each room and direct radiation in rooms under hand control.





WASHINGTON JUNIOR HIGH
Scale 1" = 64'-0"



WASHINGTON JUNIOR HIGH

Scale 1" = 64'-0"

JJH



JEFFERSON JUNIOR HIGH SCHOOL LOOKING SOUTHWEST
7/14/21




JEFFERSON JUNIOR HIGH SCHOOL LOOKING NORTHWEST
7/7/21




JEFFERSON JUNIOR HIGH SCHOOL-LOOKING EAST-
7/14/21



JEFFERSON JUNIOR HIGH SCHOOL - LOOKING
NORTH EAST 7/14/21







JEFFERSON JUNIOR HIGH

Scale 1" = 64'-0"

Exit = ◇



THIRD FLOOR PLAN



SECOND FLOOR PLAN

JEFFERSON JUNIOR HIGH

Scale 1" = 64'-0"

MON.
JH



MONROE JUNIOR HIGH SCHOOL - FOUNDATION WALLS
LOOKING SOUTHEAST

5/25/21



MONROE JUNIOR HIGH SCHOOL - FOUNDATION WALLS
LOOKING SOUTH

5/25/21




MONROE JUNIOR HIGH SCHOOL - FOUNDATION WALLS
LOOKING EAST

5/25/21



MONROE JUNIOR HIGH SCHOOL - FOUNDATION WALLS
LOOKING SOUTHWEST

5/25/21



SCHOOL NO. 15.

Area of building	16 288 s.f.
" " schoolground	17 678 "
" " playground	56 732 "
" lot	90. 698 "

MONROE JUNIOR HIGH SCHOOL

MONROE JR. HIGH

Area of building	85 974 s.f.
" " schoolground	67 715 "
" " lot	153 689 "

MAD
JH



MADISON JUNIOR HIGH SCHOOL
FRONT ELEVATION
LOOKING NORTH

5/26/21



MADISON JUNIOR HIGH SCHOOL
VIEW FROM S.E. COR. 3RD FLOOR SHOWING STRIKERS
AND POLICEMEN IN EPWORTH ST. LOOKING SOUTHEAST


5/26/21




MADISON JUNIOR HIGH SCHOOL
CONTRACTOR'S ELEVATOR
LOOKING WEST

5/26/21


16



Area of building	85 655 s.f.
" " schoolground	93 319 "
" " lot	178 974 "



FIRST FLOOR PLAN




BASEMENT FLOOR PLAN


MADISON JUNIOR HIGH

Scale 1" = 64'-0"

ROCHESTER, N.Y.



THIRD FLOOR PLAN




SECOND FLOOR PLAN

MADISON JUNIOR HIGH

Scale 1" = 64'-0"

ROCHESTER, N.Y.



401-Band Room
401A-Store Room
401B-Store Room
401C-Store Room

MADISON JUNIOR HIGH

Scale 1" = 64'-0"


ROCHESTER, N.Y.

BR'N-
CROFT

(51)

DORCHESTER RD.

NEWCASTLE RD.



Area of building	s. f.
• • schoolground	"
• • lot	276 952 "

OLD
8

OLD NO. 8 SCHOOL

St. Paul Street near Driving Park Ave.

When the village of Carthage was made a part of the City of Rochester, the little village school became a District School No. 8. It was situated on the west side of St. Paul St. north about a quarter of a mile below Driving Park Ave. bridge on a narrow lot with a 30 foot front and running back to the river bank. The school was used a number of years in its original form, except for occasional repairs, with a small but gradually increasing attendance. In 1855, the average attendance was 70 pupils--far more than the little house could accommodate--and the Board of Education decided that a new building was necessary. Accordingly on October 7, 1855, the City purchased from Albert W. Chipinan a 25 foot strip of his land, adjoining the former lot on the south, for \$125.00.


The contract for building was awarded to George Sabey, after the lowest bidder, A. Hoffman, failed to submit a guarantee, who agreed to comply with the plans and specifications drawn up by Kauffman & Bissell for \$1,610.00, and the building was soon completed. The attendance increased rapidly during the ensuing years, so that in 1859, August 15th, the City purchased the remainder of Albert W. Chipinan's lot, 46 1/2 feet, for \$175.00, and there erected a large addition to the school.

OLD NO. 8 SCHOOL

(Continued)

This two story brick structure served for many subsequent years as Public School No. 8 until it finally became inadequate and was abandoned, June 1894; and new No. 8 school was built on the corner of Conkey Avenue and Avenue B March 27, 1901, a resolution was passed to sell this location to the Western New York Institute for Deaf Mutes, but they did not sell. It was turned over to the Park Board two or three years later for use as an annex to the Seneca Park Zoo.

N. B. For above information refer to proceedings of Board of Education filed in Mr. Mullan's office of dates August 20, September and October, 1855; August 1859; August 1894; March 27, 1901.



SCALE 1" = 200'

OLD
11

OLD NO. 11 SCHOOL

Corner of Chestnut St. and James St.

The district school No. 11 situated on the corner of Chestnut and James Streets, a part of the old Manhattan Square Tract, was used for many years as the public School No. 11. After the Civil War the needs became more pressing, but the Board of Education was not in a position to build conveniently at that time, so action was deferred until a later date. A plan was suggested at one time to consolidate Nos. 11 and 12 Schools and erect one large school, but this resolution was subsequently rescinded, and though a new No. 12 School was built, the old No. 11 remained.


In 1876 plans were considered and a resolution was adopted to advertise for bids for erection of a school, the cost of which should not exceed \$10,000.00. On May 29, 1876, the contract for the new school was awarded to John J. Burke, lowest bidder, at \$9,990.00. The building was erected according to the plans of J. A. Warner and at the Board meeting March 19, 1877, it was announced complete and ready for use.

OLD NO. 11 SCHOOL

(Continued)

It was a firm two story brick structure surmounted by a tower. The final cost as announced at the above board meeting was \$10,996.45. At the close of the school year in 1901 the building was discontinued as a grammar school and used for a time as the high school annex. In 1908 the Rochester Health Bureau made its head quarters in this building.

N. B. For above information refer to proceedings of Board of Education filed in Mr. Mullén's office, dates March and May, 1876; March 19, 1877; April 13, 1901.



OLD NO. 16 SCHOOL


Near Junction of Hudson Ave. and North St.

On the 1st of October, 1849, the Board of Education resolved to outline a new school district which should be designated district No. 16. Early in 1850, therefore, they purchased four lots of the E. B. Sherman tract, Lots Nos. 204-205 fronting on North St. and Lots Nos. 213-214 fronting on Hudson Avenue, for \$175.00. This site was located near the junction of North Street and Hudson Avenue, just north of the First German Methodist Church.

The contract for the school building was awarded July 22, 1850, to F. C. Lauer for the sum of \$3,167.00. Payment for the land was deferred for a long time until Shearman demanded \$1200.00 in February, 1858.

The school was a two story brick structure facing North Street with a rear entrance from Hudson Avenue. It was discontinued in June, 1893 and two years later reopened as a truant school; it was used for this purpose for several years before it was finally sold to a manufacturing concern.

N. B. For the above information refer to the proceedings of the Board of Education filed in Mr. Mullan's office; more specifically the minutes of meetings October 1, 1849; June, July, 1850; December 31, 1857; January, 1858; March, 1893; August, 1895.



OLD
HIGH

ROCHESTER HIGH SCHOOL

OR

ROCHESTER FREE ACADEMY

At a meeting of the Board of Education July 13, 1857, the question of a greatly needed central high school was considered, and a resolution was adopted to alter school House No. 1 on Fitzhugh St. providing two more recitation rooms on the first floor, one on the second, and partition dividing rear room on this floor into two. This would make a two story brick building of eight rooms. The contract for this addition was awarded to Thomas Williamson for the sum of \$2,035.00, and the work was to be completed by Sept. 7, 1857. The new high school was opened that fall with 145 pupils.

On November 29, 1859 some repairs were ordered which were occasioned by a small fire of little consequence. In November, 1860, a brick walk was constructed in front of the high school, iron fences were set up, and a flag pole erected.

On April 22, 1861, in answer to a letter from the State Regents, the building was described as a two story brick structure, assessed at \$18,000.00 and accommodating 225 pupils; and this building was incorporated under the State Regents as an Academy, Rochester Free Academy

For a year and a half, 1872-3, the school was temporarily held on the third and fourth floors of the Masonic building, while a new Rochester Free Academy was being built on the same location with the \$75,000.00 appropriation for this purpose.

ROCHESTER FREE ACADEMY

(Continued)

They paid an annual rental of \$2500.00 for the use of their quarters in the Masonic Building and held just one session, from 9 until 1:30 daily, to save the children from walking up and down stairs.

Construction of the new building was delayed for some time because of the inability of the city to obtain property belonging to Mr. Palmer, but on March 16, 1874 the new building was reported ready for occupancy and the transfer from the Masonic building was made immediately.

This new building was modern and well equipped, and it fulfilled the requirements of the city for years, until the present East High School was completed in 1903 and West High School a year or two later. It was then abandoned as a school and became the City Municipal Building.

NIBROC BOND

MAIN ST. W.

MONTGOMERY AL.

SO. FITZHUGH ST.



MUNICIPAL
BUILDING

165'


99'

99'


ERIE CANAL

1" = 50'

OUTSIDE
SCHOOLS



NEW CENTRAL HIGH SCHOOL - WASHINGTON D.C.
6/12/21



NEW CENTRAL HIGH SCHOOL - WASHINGTON D.C.
6/12/21



LOOKING SOUTH FROM SMITH ST. BRIDGE



LOOKING NORTH FROM SMITH ST. BRIDGE



3 9077 04046425 0